

Property of KOSCIUSKO COUNTY
SURVEYORS OFFICE
Address 100 W CENTER ST.
COURTHOUSE WARSAW, IN
Telephone _____
MICHAEL KISSINGER - SURVEYOR

TOPCON GPT-3105 W TOTAL STATION

This Book is manufactured of a High Grade
50% Rag Ledger Paper having a Water Resist-
ant Surface, and is sewed with Nylon Water-
proof Thread.

815260



SECTION CORNER FIELD BOOK 8

INDEX

STARTED OCTOBER 6, 2017

TIPPECANOE E $\frac{1}{4}$ CORNER SECTION	19-33-7	1
TIPPECANOE SE CORNER SECTION	19-33-7	2
ETNA CENTER OF SECTION	35-33-4	3
ETNA W $\frac{1}{4}$ CORNER SECTION	35-33-4	4
ETNA W $\frac{1}{4}$ CORNER SECTION	27-33-4	5
WAYNE CENTER OF SECTION	11-32-6	6
JACKSON SE CORNER SECTION	14-30-7	7
JACKSON S $\frac{1}{4}$ CORNER SECTION	14-30-7	8
JACKSON SW CORNER SECTION	14-30-7	9
JACKSON W $\frac{1}{4}$ CORNER SECTION	14-30-7	10
JACKSON NW CORNER SECTION	14-30-7	11
WAYNE CENTER OF SECTION	11-32-5	12
PRAIRIE CENTER OF SECTION	16-33-5	13
PRAIRIE E $\frac{1}{4}$ CORNER SECTION	16-33-5	14
WAYNE E $\frac{1}{4}$ CORNER SECTION	29-32-6	15
PRAIRIE W $\frac{1}{4}$ CORNER SECTION	20-33-5	16
HARRISON W $\frac{1}{4}$ CORNER SECTION	3-32-5	17
TURKEY CREEK SW CORNER SECTION	27-34-7	18
TURKEY CREEK W $\frac{1}{4}$ CORNER SECTION	27-34-7	19
TURKEY CREEK NW CORNER SECTION	27-34-7	20
TURKEY CREEK SE CORNER SECTION	27-34-7	21

Prop

Addr

Tele

M.c

Te

This
50%
ant
proc

TURKEY CREEK NE CORNER SECTION 27-34-7	22
PRAIRIE CENTER OF SECTION 35-33-5	23
TIPPECANOE S $\frac{1}{4}$ CORNER SECTION 19-33-7	24
SEWARD NE CORNER SECTION 26-31-5	25
HARRISON CENTER OF SECTION 14-32-5	26
WAYNE E $\frac{1}{4}$ CORNER SECTION 27-32-6	27
VAN BUREN SW CORNER SECTION 8-34-6	28
VAN BUREN N $\frac{1}{4}$ CORNER SECTION 8-34-6	29
VAN BUREN NE CORNER SECTION 8-34-6	30
TURKEY CREEK E $\frac{1}{4}$ CORNER SECTION 27-34-7	31
TURKEY CREEK W $\frac{1}{4}$ CORNER SECTION 23-34-7	32
TURKEY CREEK N $\frac{1}{4}$ CORNER SECTION 27-34-7	33
TIPPECANOE CENTER OF SECTION 28-33-7	34
JACKSON E $\frac{1}{4}$ CORNER SECTION 32-31-7	35
JACKSON NW CORNER SECTION 32-31-7	36
CLAY NW CORNER SECTION 25-31-6	37
SEWARD CENTER OF SECTION 36-31-5	38
SEWARD E $\frac{1}{4}$ CORNER SECTION 36-31-5	39
PLAIN E $\frac{1}{4}$ CORNER SECTION 31-33-6	40
WAYNE E $\frac{1}{4}$ CORNER SECTION 28-32-6	41
SEWARD W $\frac{1}{4}$ CORNER SECTION 36-31-5	42
LAKE NE CORNER SECTION 6-30-6	43
VAN BUREN SW CORNER SECTION 21-34-6	44
WAYNE E $\frac{1}{4}$ CORNER SECTION 8-32-6	45
HARRISON W $\frac{1}{4}$ CORNER SECTION 35-32-5	46

TIPPECANOE	S $\frac{1}{4}$ CORNER SECTION 34-33-7	47
TIPPECANOE	COS SECTION 34-33-7	48
HARRISON	E $\frac{1}{4}$ CORNER SECTION 3-32-5	49
HARRISON	COS SECTION 3-32-5	50
HARRISON	N $\frac{1}{4}$ CORNER SECTION 3-32-5	51
HARRISON	N $\frac{1}{4}$ CORNER SECTION 10-32-5	52
HARRISON	S $\frac{1}{4}$ CORNER SECTION 4-32-5	53
SEWARD	E $\frac{1}{4}$ CORNER SECTION 26-31-5	54
TURKEY CREEK	CENTER OF SECTION 18-34-7	55
CLAY	NW CORNER SECTION 19-31-6	56
CLAY	W $\frac{1}{4}$ CORNER SECTION 19-31-6	57
CLAY	SW CORNER SECTION 19-31-6	58
ETNA	SE CORNER SECTION 2-33-4	59
ETNA	E $\frac{1}{4}$ CORNER SECTION 2-33-4	60
ETNA	NE CORNER SECTION 2-33-4	61
SCOTT	SW CORNER SECTION 36-34-4	62
SEWARD	SE CORNER SECTION 25-31-5	63
SEWARD	S $\frac{1}{4}$ CORNER SECTION 25-31-5	64
MONROE	S $\frac{1}{4}$ CORNER SECTION 2-31-7	65
MONROE	SW CORNER SECTION 1-31-7	66
MONROE	S $\frac{1}{4}$ CORNER SECTION 1-31-7	67
MONROE	SE CORNER SECTION 1-31-7	68
PRAIRIE	N $\frac{1}{4}$ CORNER SECTION 21-33-5	69
FRANKLIN	NW CORNER SECTION 15-31-4	70

FRANKLIN	W $\frac{1}{4}$ CORNER SECTION 15-31-4	71
TURKEY CREEK	NE CORNER SECTION 18-34-7	72
TURKEY CREEK	N $\frac{1}{4}$ CORNER SECTION 18-34-7	73
TURKEY CREEK	NW CORNER SECTION 18-34-7	74
TURKEY CREEK	COS SECTION 19-34-7	75
PLAIN	S $\frac{1}{4}$ CORNER SECTION 30-33-6	76
PLAIN	SW CORNER SECTION 30-33-6	77
TURKEY CREEK	S $\frac{1}{4}$ CORNER SECTION 18-34-7	78

DESCRIPTION

BEARING DISTANCE

NAIL IN B. CAP IN POWER POLE

NNW 20.60'

⊥ RR RAIL FCP

N 20.6'

⊥ RR RAIL FCP

SE 20.7'

⊥ RR RAIL FCP

S 32.55'


NAIL IN B. CAP IN ANCHOR POLE

S 34.43'

⊥ RR RAIL FCP

SW 24.6'

TIPPECANOE



DESCRIPTION

BEARING DISTANCE

2" DIA STEEL FENCE POST

N

1.6'

FD 5/8" REBAR NO CAP

S

10.0'

"STEEL FENCE POST - ANGLE IRON" RSK & MEK 10/21/96

"WALKER" SURVEY MARCH 6, 2001 DOC # 2001071796

TIPPECANOE

2

10/5/17
SRMSE CORNER
SECTION 19.33.7
TIPPECANOE TWP PT

FIELD

x x

WOODED
AREAFD 2" ANGLE
IRON FCP

McKENNA ROAD

O 5/8" REBAR NO CAP


DESCRIPTION

BEARING DISTANCE

16" SQ CONCRETE FENCE CORNER POST E 20'

"KIMPEL" SURVEY JULY 15, 2003 Doc # 2003071293
 "KIMPEL" SURVEY APRIL 2, 2001 Doc # 2001072034

3



DESCRIPTION


BEARING DISTANCE

NAIL IN B. CAP IN POWER POLE	N	20.53'
2" DIA STEEL FCP LEANING EAST (BASE)	N	22.6'
3/4" SQ HEAD RR BOLT 2" DEEP	E	2.65'
NAIL IN B. CAP IN POWER POLE	S	25.98'
¢ RR RAIL FCP	S	22.0'
1/2" x 16" REBAR W/CAP S. 2' TO E/P	SW	27.54'

"KIMPEL" SURVEY APRIL 2, 2001 DGC # Z001072034

ETNA

4



DESCRIPTION

BEARING DISTANCE

72" DIA OAK TREE

W 26'

10" DIA WOOD FENCE POST


E 3.3'

"WALKER" SURVEY 12/4/2007 Doc # 200800000303

"WALKER" SURVEY 7/11/2005 Doc # 200500009782

ETNA

5

10/10/17
JRMW 1/4 CORNER
SECTION 27.33.4
ETNA TWP PT 70


DESCRIPTION

BEARING DISTANCE

SHADOW LAKES EST SECTION 3 PLAT BOOK 13 P 18

WAYNE

6



CENTER OF SECTION
SECTION 11-32-6
WAYNE TWP RT 52

FO RR RAIL
FENCE CORNER POST


DESCRIPTION	BEARING	DISTANCE
NAIL IN B. CAP WABASH CO		
REMC P. POLE #71073	NE	31.06'
SW CORNER 3" ANGLE IRON FCP	NE	29.73'
WABASH CO WITNESS SHAFT	SE	35.40'
WABASH CO WITNESS SHAFT	SW	39.51'

SHAD


"WOOLPERT" STA #880 3/15/02

JACKSON

7



SE CORNER
SECTION 14-30-7
JACKSON TWP RT KA



DESCRIPTION	BEARING	DISTANCE
NAIL IN B. CAP WABASH CO REMC POLE 71534	ESE	68.85'
WABASH CO WITNESS SHAFT	NE	21.61'
WABASH CO WITNESS SHAFT	SE	20.71'
WABASH CO WITNESS SHAFT	SW	21.50'


SURVEY RECORD BOOK 2 (COPY) P. 210 6/11/1910 -

JACKSON

8



S 1/4 CORNER
SECTION 14-30-7
JACKSON TWP PT 140



FD WABASH COUNTY
MONUMENT
2" ALUMINUM
2" DEEP
SET ON MAY 20, 1992

STONE

DESCRIPTION	BEARING	DISTANCE
WABASH CO WITNESS SHAFT	SW	35.35'
WABASH CO WITNESS SHAFT	W	18.25'
3" DIA STEEL FCP 2" DEEP	N	20.65'


JACKSON

9



10/16/17
DRM

SW CORNER
SECTION 14-30-7
JACKSON TWP PT 139



WABASH COUNTY

WABASH COUNTY
MONUMENT
2" ALUMINUM
4" DEEP

DESCRIPTION

NAIL IN B. CAP IN POWER POLE
 E RR RAIL FCP
 NAIL IN B. CAP IN POWER POLE


BEARING DISTANCE

WNW 78.40'
 NW 48.0'
 NNW 77.40'

"McCREA" SURVEY 2/4/2009 Doc # 2010050271

JACKSON

10




DESCRIPTION

BEARING DISTANCE

4 3"Ø1/4 STEEL FCP	W	25.1'
NAIL IN B. CAP IN POWER POLE	W	17.51'
1/2" x 16" REBAR W/CAP 8.2' TO E/P	NE	33.20'
1/2" x 16" REBAR W/CAP 7.4' TO E/P	SE	34.51'
4 RR RAIL FCP	SE	24.7'

JACKSON

11

10/16/17
JRMNW CORNER
SECTION 14-30-7
JACKSON TWP PT 113

[illegible]

WAYNE

12

CENTER OF SECTION
SECTION 11-32-5
WAYNE TWP PT 64

10/18/17
JRM

AREA

WOODED

CORN FIELD

FD RR RAIL FCP


DESCRIPTION

BEARING DISTANCE

€ 8" DIA CONC FILLED STEEL FENCE POST	NW	24.55'
€ RR RAIL FCP	N	15.29'
€ 5" DIA STEEL FCP	S	15.32'

PRAIRIE

13




DESCRIPTION

BEARING DISTANCE

1/2" x 16" REBAR w/CAP 5.7' TO E/P	NE	24.86'
NAIL IN B. CAP NIPSCO P. POLE 639/044	E	22.85'
1/2" x 16" REBAR w/CAP 9.4' TO E/P	SE	27.42'

PRAIRIE

14





E 1/4 CORNER
SECTION 29-32-6
WAYNE TWP RT 153

FENCE
X X
REMAINS

AREA

WOODED

FD 1 1/2" DIA IRON PIPE
4' TALL
INSIDE A 3 1/2" RUSTED
OF STEEL FCP

"LONG" SURVEY 2/20/1995 #95-03-0649

DESCRIPTION		BEARING	DISTANCE
1/2" X 16" REBAR W/CAP	10' TO E/P	SW	36.05'
⊥ RR RAIL FCP		W	20.41'
⊥ RR RAIL FCP		E	20.47'
NAIL IN B. CAP IN POWER POLE		SE	27.29'

SURVEY FILE BOOK 1 Pg 23 1962 G. NYE
 "WALKER" SURVEY 7/18/2003 #2003110538
 "MICHEL" SURVEY 1/9/2007 #200700014893


PRAIRIE

16



10/24/17
DEM

W/4 CORNER
 SECTION 20-33-5
 PRAIRIE TWP PT 102




FO 1" DK NAIL
 FLUSH

REPLACED IT WITH A
 RR SPIKE



10/24/17
JRM

W 1/4 CORNER
SECTION 3-32-5
HARRISON TWP RT 14



FO 3" DIA CONC FILLED
STEEL FCP WITH
A 6" DIA SCH 40 PIPE
OVER TOP

"MICHEL" SURVEY 12/21/05 # 200600000698

DESCRIPTION


BEARING DISTANCE

E RR RAIL FCP	W	21.1'
NAIL IN B. CAP REMC POLE 4879	W	19.18'
"WALKER" CAPPED IRON	E	19.92'
NAIL IN B. CAP WOOD GATE POST	SE	36.19'

"MICHEL" SURVEY 3/31/06 # 200600006072

TURKEY CREEK

18



DESCRIPTION


BEARING DISTANCE

NAIL IN B. CAP REMC POLE 4961	WNW	96.20'
1/2" x 16" REBAR w/CO CAP AT EDGE PAV	NW	40.57'
NAIL IN B. CAP REMC POLE 4962	NNW	58.98'
INSIDE NE CORNER 5 1/2" x 10" B. BEAM POST	SSW	50.40'
1/2" x 16" REBAR w/CO CAP AT EDGE PAV	SW	32.63'
INSIDE NE CORNER 5 1/2" x 10" B. BEAM POST	WSW	49.02'

"KEMPER" SURVEY 8/24/04 #200400015464

TURKEY CREEK

19



DESCRIPTION

BEARING DISTANCE

FD PK NAIL NIPSCO POLE 661/546	WNW	27.95'
FD 1/2" REBAR w/co CAP 7.0 TO E/P	NW	25.05'
FD 1/2" REBAR w/co CAP 6.7 TO E/P	NE	21.70'
FD 1/2" REBAR w/co CAP	SE	39.25'
FD MAG NAIL NIPSCO POLE 661/547	SW	73.88'


6/16/2004 MEK

CHECKED & UPDATED 10/25/17 JRM

"KEMPER" SURVEY 8/24/2004 #200400015464

TURKEY CREEK


20



DESCRIPTION	BEARING	DISTANCE
1/2" X 16" REBAR W/CO CAP 9.2' TO E/P	NW	30.33'
S FACE 2" ANGLE IRON FCP AT BASE	N	19.8'
4 RR RAIL FCP	S	20.1'
NAIL IN B. CAP POWER POLE	WSW	94.49'

TURKEY CREEK

21




DESCRIPTION

BEARING DISTANCE

1/2" x 16" REBAR w/CAP 3.6 TO E/P	SW	35.20'
1/2" x 16" REBAR w/CAP 4.5 TO E/P	ENE	49.43'
1/2" x 16" REBAR w/CAP 10' TO E/P	SE	41.00'

PRAIRIE


23

10/26/17
JRMCENTER OF SECTION
SECTION 35-33-5
PRAIRIE TWP PT 147

11/2/17
DRM






S 1/4 CORNER
SECTION 19.33-7
TIPPECANOE TWP RT




FIELD

FIELD




FDRR RAIL
FCP

DESCRIPTION	BEARING	DISTANCE
8.5' TO E/P		
1/2" X 16" REBAR W/CAP SPLIT BETWEEN POSTS	NW	41.54'
1/2" X 16" REBAR W/CAP 4.3' S OF RR RAIL	NE	38.93'
NAIL IN B. CAP IN POWER POLE	SSW	64.29'
NAIL IN B. CAP IN POWER POLE	WSW	47.31'
OLD TIES FROM CLAMP FILE		
RIP 42.8' NE	NE	42.8' ✓
BRIDGE ROW 44.4' SE (5 1/2" X 10 1/2" POST)	SE	44.4' ✓
" " 44.15' SW (NEAREST CORNER)	SW	44.15' ✓
" " 43.93' NW (NEAREST CORNER)	NW	43.6'



11/13/17
DEM

CENTER OF SECTION
SECTION 14-32-5
HARRISON TWP PT



DESCRIPTION


BEARING DISTANCE

1/2" x 24" REBAR w/CAP 5.1' to E/P	SW	25.43'
NAIL IN B. CAP IN POWER POLE	NE	58.05'
1/2" x 24" REBAR w/CAP 4.7' to E/P	SE	26.21'

"WALKER" SURVEY 10/5/2011 Doc # 201100133 - RR SPIKE

WAYNE

27



DESCRIPTION

4" x 8" I-BEAM POST
WEST END OF FRAME CHICKEN COOP
8" CONC FENCE CORNER POST


BEARING DISTANCE

WSW 17'
E 11'
W 108'

"WALKER" SURVEY JAN 15, 1996 #96-04-0613

VAN BUREN

28



SW CORNER
SECTION 8-34-6
VAN BUREN TWP RT 55

FD 3/4" IRON PIPE
2" ABOVE GRND
4. 2' NORTH OF FENCE

DESCRIPTION

BEARING DISTANCE

STEEL FENCE POST

N

4.2'

"KIMPEL" SURVEY 10/6/2010 # 2010100277

VAN BUREN

29

11/16/17
SRM
N

N 1/4 CORNER
SECTION 8-34-6
VAN BUREN TWP R 30

PRESTON MILES DITCH
TOP OF BANK

CORN FIELD

FO CUT OFF RAILROAD
RAIL FENCE CORNER
POST
12" DEEP

DESCRIPTION

BEARING DISTANCE

1/2" x 24" REBAR W/CAP 17.2' TO RR $\perp$	NE	27.96'
$\perp$ RAILROAD TRACKS	E	32.25'
1/2" x 24" REBAR W/CAP 17.6' TO RR $\perp$	SE	28.97'

OLD TIES

 $\perp$ RAILROAD 32.0 EAST

"WALKER" SURVEY JUNE 15, 2005 # 200500009792

VAN BUREN

30

11/16/17
DRMNE CORNER
SECTION 8-34-6
VAN BUREN TWP RT 31

CORN FIELD

EDGE
OF FIELDFO IRON MONUMENT
1" SHAFT W 2" DIA HEAD
12" DEEP

48.5'

11/17/17
JRM

E¹/₄ CORNER
SECTION 27-34-7
TURKEY CREEK TWP PT 122

N

CORN
FIELD

FENCE REMAINS

FARM LANE

GRASS

FD RAILROAD RAIL
FCP

DESCRIPTION

BEARING DISTANCE


1/2" x 24" REBAR W/CAP 10.3' TO E/P	SW	33.10'
¢ OF A 2 1/2" DIA STEEL FCP	W	21.2'
FO PK NAIL IN NIPSCO P. POLE ⁶⁶⁷ / ₃₄₉	NW	57.58'
NAIL IN B. CAP IN NIPSCO P. POLE ⁶⁵⁷ / ₉₈₁	ESE	19.30'

LOUIE D. MOORES 5TH ADD TO HIGHLAND VIEW GARDENS

"WALKER" SURVEY NOV 6, 2000 # 2001010283

TURKEY CREEK

32



DESCRIPTION

BEARING DISTANCE

FO MAG NAIL IN NIPSCO P POLE $\frac{689}{707}$	NW	33.81'
4 OF A 5" DIA STEEL FCP	NW	34.95'
SOUTH FACE 12" X 12" I-BEAM POST	N	27.55'
FO PK NAIL IN NIPSCO P POLE $\frac{689}{708}$	ESE	70.15'
FO MAG NAIL IN ASPHALT	SE	22.02'
NAIL IN B. CAP IN NIPSCO P POLE $\frac{1063}{120}$	SSE	62.78'

MAG NAIL NO TAGS N 7.26'

2/22/17 FO 3/4" SQ X 16" STEEL BAR 4" DEEP DUG A

2' X 2' HOLE 24" DEEP, NOTHING ELSE FO

SURVEY RECORD BOOK 4 P. 275 8/18/1931

SURVEY RECORD BOOK 3 P. 423 10/10/1945

"KIMPEL" SURVEY MAY 21, 2002 # 200209095Z


"ANDERSON" SURVEY FEB 29, 2000 # 2000-02-1116

TURKEY CREEK

33

11/17/17
DEM

N 1/4 CORNER
SECTION 24-34-7
TURKEY CREEK TWP PT 90



2/22/17 FO RR SPIKE
4" DEEP OVER A 3/4" X 16"
BOAT SPIKE 10" DEEP
DUG A 2' X 2' HOLE
24" DEEP, NOTHING ELSE FO

11/17/17 SET MAG NAIL W/CO TAG


DESCRIPTION

BEARING DISTANCE

FO PK NAIL IN TEL POLE LEAVING NORTH	N	16.98'
FO PK NAIL IN POWER POLE	SW	27.82'
FO PK NAIL IN POWER POLE	SSW	58.40'

TIPPECANOE

34



DESCRIPTION


BEARING DISTANCE

1/2" x 24" REBAR W/CAP 11' TO E/P	SW	22.65'
4 6" WOOD FCP	W	22.1'
NAIL IN B. CAP REMC POLE #5389	NE	25.10'
4 RZR RAIL FCP	E	20'
1/2" x 24" REBAR W/CAP 10' TO E/P	SE	25.67'

SURVEY RECORD BOOK 2 (COPY) P. 369 - STONE

JACKSON

35




DESCRIPTION

BEARING DISTANCE

FO "WALKER" MAG NAIL w/TAG FLUSH	W	20.05'
FO "WALKER" CAPPED IRON	N	19.98'
4 6" DIA CONC FILLED FCP	NE	27.0'
NAIL IN B. CAP IN POWER POLE	SW	26.22'

JACKSON

36



DESCRIPTION


BEARING DISTANCE

NAIL IN B. CAP IN POWER POLE	WNW	51.54'
4 RR RAIL FCP	NNW	42.0'
NAIL IN B. CAP IN POWER POLE	NNW	62.10'
4 RR RAIL FCP	NNE	42.3'
NAIL IN B. CAP IN POWER POLE	SE	52.58'
1/2" x 24" REBAR W/ CO CAP 12.1' TO E/P	SW	31.26'

SURVEY RECORD BOOK 4 P. 110 - STONE 4/1/1891
 "LONG" SURVEY 11/30/2000 #2000111400 - PK NAIL

CLAY

37



DESCRIPTION


BEARING DISTANCE

1/2" x 24" REBAR w/ CAP 8.5' TO E/P	NW	25.96'
NAIL IN B. CAP IN POWER POLE	NNE	22.64'
1/2" x 24" REBAR w/ CAP 9.5' TO E/P	NE	42.35'

"WALKER" SURVEY 10/5/1998 # 98-11-1634

SEWARD

38



DESCRIPTION


BEARING DISTANCE

1/2" x 24" REBAR w/CAP 7 TO E/P	NW	27.32'
1/2" x 24" REBAR w/CAP 15.5 TO E/P	NE	36.75'
1/2" x 24" REBAR w/CAP 4.2 TO E/P	SE	17.28'

"WALKER" SURVEY 8/20/2009 # 2009110469

SEWARD

39




"WALKER" SURVEY APRIL 2, 1998 # 1998-07-0490
DEED RECORD 224 Pg 516

PLAIN

40

11/30/17
DEM
N

E 1/4 CORNER
SECTION 31-33-6
PLAIN TWP PT



DESCRIPTION

BEARING DISTANCE

0 CHAIN LINK FENCE


S 27.3'

WAYNE

41

12/1/17
JRM

E 1/4 CORNER
SECTION 28-32-6
WAYNE TWP PT 151



FO 1 1/4" IRON PIPE INSIDE A
2" DIA STEEL FCP

FOXWOOD ESTATES PLAT BOOK 13 Pg 16 8/9/2005

DESCRIPTION


BEARING DISTANCE

DESCRIPTION	BEARING	DISTANCE
FO 3/4" IRON PIPE, THREADED END	W	77' ±
FO 1/2" IRON PIPE 8" ABOVE GROUND	E	90' ±
BOTH 1 PIPES IN EXISTED E-W FENCE LINE		

LAKEVIEW ACRES PLAT BOOK 7 P. 79 3/16/78
 ORIGINAL FIELD NOTE BOOK P. 162
 INTERSECTED N. BOUNDARY 118 LKS WEST OF POST

LAKE

43



DESCRIPTION


BEARING DISTANCE

FO NAIL IN B. CAP NIPSCO POLE $537/922$ WNW 53.19'
 MAG NAIL IN NIPSCO POLE $686/618$ NE 33.82'
 $1/2 \times 24$ " REBAR W/CAP 2' NORTH OF RR MON SE 54.46'
 NAIL IN B. CAP NIPSCO POLE $651/496$ SSE 80.49'

"WALKER" SURVEY 1/21/2009 #2009010528

VAN BUREN

44



DESCRIPTION


BEARING DISTANCE

FO 1/2" CAPPED IRON (CO WIT)	NE	49.92'
FO 1/2" CAPPED IRON (CO WIT)	NW	50.36'
SET NAIL IN B. CAP NIPSCO PPole ⁶²³ 905	SSW	21.37'
SOUTH RIM OF MANHOLE	N	11.5'

STONE LOCATED 12" DEEP - 11/1/2011 RSK & MEK
6/6/18 - SET HARRISON MONUMENT - JRM

WAYNE

45



DESCRIPTION	BEARING	DISTANCE
NAIL IN B. CAP IN POWER POLE	NW	36.53'
1/2" x 16" REBAR W/CAP 10' TO E/P	NE	41.43'
NAIL IN B. CAP IN POWER POLE	ENE	67.90'
4 RR RAIL FCP	SE	32.3'

SURVEY RECORD BOOK 2 (COPY) Pg 170 OCT 19, 1859
STONE " Pg 170 MAY 1, 1937


"BROWER" SURVEY MARCH 29, 1976 SURVEY RECORD BOOK
(RR SPIKE) 28 Pg 67

HARRISON

46

12/21/17
JRM
N

W 1/4 CORNER
SECTION 35-32-5
HARRISON TWP PT 165



DESCRIPTION

BEARING


DISTANCE

NAIL IN B. CAP IN POWER POLE	WNW	78.80'
NAIL IN B. CAP IN NIPSCO POLE ⁶²⁴ /475	NW	61.78'
FD MAG NAIL IN CO TAG IN POWER POLE	ENE	75.85'
NAIL IN B. CAP NIPSCO POLE ⁶²⁴ /476	SW	59.83'
E CONC STATE HIGHWAY R/W MON	SW	65.6'
& PAVEMENT STR RD 13	E	2.7'


"KEMPER" SURVEY 5/28/2010 - HARRISON MONUMENT

TIPPECANOE

47




S 1/4 CORNER
SECTION 34-33-7
TIPPECANOE TWP R 164



DESCRIPTION	BEARING	DISTANCE
NAIL IN B. CAP REMC POLE 1838	E	147.5'
NAIL IN S. BARBEE ROAD	E	169.5'
OLD TIES		
I.P. 16' N (FO 1" IRON PIPE BENT 8" DEEP N 16.4'		
14" COTTONWOOD 42.8' E (FO 40" COTTONWOOD ENE 42'		

TIPPECANOE

48



"KIMPEL" SURVEY 6/9/2006 #200600009163


NO STONE CALLED FOR IN SURVEY RECORD BOOKS

HARRISON

49

1/22/18
SRM
N

E 1/4 CORNER
SECTION 3-32-5
HARRISON TWP RT 12



FD STONE PROTRUDING
FROM THE CONC BASE
OF A RAILROAD RAIL POST


1/22/18

JRM



N

CENTER OF SECTION
SECTION 3-32-5
HARRISON TWP PT 13



FO 3" DIA CONC
FILLED STEEL FCP
WITH A 6" SCH 40 PIPE
OVER TOP


"WALKER" SURVEY 12/21/2005 # 200600000698

DESCRIPTION	BEARING	DISTANCE
SOUTH FACE 12" SQ CONC FCP	N	19.95'
1/2" x 24" REBAR W/CAP 11.7' TO E/P	NE	27.60'
NAIL IN B. CAP IN POWER POLE	SE	52.32'

"WALKER" SURVEY 12/21/2005 #200600000698

HARRISON

51



N 1/4 CORNER
SECTION 3-32-5
HARRISON TWP PT 8

FO SMALL MAG NAIL 2" DEEP

NO OTHER BEADING, REPLACED
WITH MAG NAIL W/ CO TAG

DESCRIPTION

BEARING DISTANCE

1/2" x 16" REBAR W/CAP 0.45' FROM FENCE	NW	24.68'
NAIL IN B. CAP IN POWER POLE	NE	68.75'
RR RAIL FCP	S	20.50'

HARRISON

52



1/22/18
JRM

N 1/4 CORNER
SECTION 10-32-5
HARRISON TWP PT 33

CR 100 N
20.6' ASPH

YARD

FO REMAINS OF RR
SPIKE. NO OTHER READING

RESET NEW SPIKE

"BROWER" 6/15/1966 - SET RR SPIKE, RAIL POST 20.4 S


DESCRIPTION

BEARING DISTANCE

1/2" x 16" REBAR W/CAP 9.5' TO E/P	NW	31.48'
RAILROAD RAIL FCP	N	20.1'
NAIL IN B. CAP IN POWER POLE	NNE	21.18'
NAIL IN B. CAP IN POWER POLE	ESE	28.40'

HARRISON

53



"WALKER" SURVEY 2/5/2004 # 2004.0000 1904

DESCRIPTION

BEARING DISTANCE


NAIL IN B. CAP IN POWER POLE	NW	31.36'
NAIL IN B. CAP IN REMC POLE 8777	ENE	19.67'
& RR RAIL FCP	E	20.05'
NAIL IN B. CAP REMC POLE 8778	WSW	52.59'

RR SPIKE 5/26/1966 - CONC PT 20.1' W
 RIP 20.1' E
 RIP 169.3' NE

STONE - SURVEY RECORD BOOK 2 (COPY) Pg 249 9/20/1864

SEWARD

54



FO STONE 8" DEEP
 SET MAG NAIL w/co
 TAG OVER TOP

FO RR SPIKE 4" DEEP
 0.3' WEST

6/7/18 - LAID RR SPIKE ON STONE - SET HARRISON MONUMENT

DESCRIPTION	BEARING	DISTANCE
± RR RAIL FCP	W	19.93'
FO 5/8 REBAR 8" DEEP, RIBBON NO CAP	E	20.00'
NAIL IN B. CAP IN POWER POLE	SW	32.27'

TURKEY CREEK


55



1/29/18

SRM

CENTER OF SECTION
SECTION 18-34-7
TURKEY CREEK TWP PT 77




DESCRIPTION	BEARING	DISTANCE
ERR RAIL FCP LEAVING SW	SW	24.45'
NAIL IN B. CAP NIPSCO P. POLE ⁶²⁰ / ₃₂₂	SW	24.71'
ERR RAIL FCP	N	24.05'
NAIL IN B. CAP REMK P. POLE	SE	54.30'

STONE - SURVEY RECORD BOOK 3 Pg 120 - 8/16/1917
 "MICHEL" SURVEY 6/18/2008


CLAY

56



DESCRIPTION	BEARING	DISTANCE
ERR RAIL FCP	W	16.00'
ERR RAIL FCP	E	16.18'
1/2" X 16" REBAR W/ CO CAP	10.1' TO E/p SW	24.00'

CLAY




DESCRIPTION	BEARING	DISTANCE
1/2" x 16" REBAR W/CO CAP	NW	36.18'
NAIL IN B. CAP IN POWER POLE	E	14.53'
1/2" x 16" REBAR W/CO CAP	SW	32.50'

"LONG" SURVEY 3/10/1992 #92-03-1107
 STONE - SURVEY RECORD BOOK 2 (COPY) Pg 164
 8/3/1859

STONE SEARCHED FOR NOT FOUND

CLAY


58



DESCRIPTION	BEARING	DISTANCE
NAIL IN B. CAP IN POWER POLE	WNW	27.25'
± RR RAIL FCP	NW	27.5'
± RR RAIL FCP	NE	26.95'
1/2" x 24" REBAR w/ CO CAP 13.2' to E/P	SE	35.85'
1/2" x 24" REBAR w/ CO CAP 13.5' to E/P	SW	36.27'

ETNA

59




DESCRIPTION

NAIL IN B. CAP IN POWER POLE	WNW	75.90'
1/2" x 24" REBAR W/CAP	NW	38.60'
NAIL IN B. CAP IN POWER POLE	SSW	43.40'

"PLYMOUTH LAND SURVEYING" 3/17/1997 #98-02-0639

ETNA

60



DESCRIPTION

BEARING DISTANCE


NAIL IN B. CAP NIPSCO P POLE	509/511	WNW	54.62'
1/2" x 24" REBAR W/CO CAP 9.2' to E/P		NW	25.24"
FO RR SPIKE FLUSH (SCOTT TWP)		E	36.30'
NAIL IN B. CAP NIPSCO P POLE	1065/259	SSW	44.46'

APRIL 19, 1846 (36.3)
ORIGINAL FIELD NOTE BOOK Pg 468 - INTERSECTED 55 LINKS
WEST OF POST

"PLYMOUTH LAND SURVEYING" 3/17/1997 #98-02-0639
"KEMPER" SURVEY 3/31/2003 #2003032170

ETNA

61




DESCRIPTION

BEARING DISTANCE

FD 5/8" REBAR 2" DEEP (ETNA TWP)	W	36.30'
NAIL IN B. CAP NIPSCO P POLE 1065/258	NE	46.80'
1/2" x 24" REBAR w/co CAP 12' TO E/P	SSE	34.44'

SCOTT

62



DESCRIPTION

BEARING DISTANCE


E RR RAIL FCP	N	19.97'
1/2" x 24" REBAR w/CAP 12.1' TO E/P	SE	38.63'
NAIL IN B. CAP IN POWER POLE	SSW	67.17'
NAIL IN B. CAP IN POWER POLE	WSW	59.09'

LAKE VIEW PARK ON HILL LAKE - 6/1946 G. NYE


"WALKER" SURVEY 8/24/2004 # 200400018437

SEWARD

63



SE CORNER
SECTION 25-31-5
SEWARD TWP PT




DESCRIPTION	BEARING	DISTANCE
E RR RAIL FCP	N	19.95'
NAIL IN B. CAP IN POWER POLE	NE	55.54'
E CUT OFF RR RAIL FCP	S	20.03'

"WALKER" SURVEY 8/24/2004 # 200400018437

SEWARD

6A




FD 1 1/2" PK NAIL 2" DEEP
 REMOVED NO OTHER READING
 REPLACED WITH RR SPIKE
 2/14/18 REPLACED SPIKE
 WITH MAG NAIL w/CO TAG

DESCRIPTION	BEARING	DISTANCE
1/4 STATE ROAD 13	N	89.5'
NAIL IN B. CAP IN POWER POLE	ESE	76.24'
1/2" x 24" REBAR w/ CAP 6" TO E/P	SE	37.81'
1/4 RR RAIL FCP	SW	34.95'
NAIL IN B. CAP IN POWER POLE	SW	28.91'
FO 4" CUT IN CONC HEADWALL	NW	44.80'


"MICHEL" SURVEY AUG 30, 2013 # 2013110312

MONROE

65



S 1/4 CORNER
SECTION 2-31-7
MONROE TWP PT 36




DESCRIPTION

BEARING DISTANCE

1/2" x 24" REBAR w/ CAP 10.5' TO E/P	NW	35.62'
NAIL IN B. CAP IN POWER POLE	N	15.87'
NEAREST EDGE 3" x 12" I-BEAM POST	SSE	53.0'
NAIL IN B. CAP IN POWER POLE	SSE	75.18'

"WALKER" SURVEY 8/10/1995 #95-12-0041
 "MICHEL" SURVEY MARCH 7, 2013 #2013091083

666




DESCRIPTION

BEARING DISTANCE

NAIL IN B. CAP IN POWER POLE	WNW	57.87'
NAIL IN B. CAP IN POWER POLE	NNW	62.87'
E RR RAIL FCP	S	22.68

MONROE

67



"BURLAGE" SURVEY FEB 2 1993 *93-03-0163
 "WALKER" SURVEY AUG 10 1995 *95-12-0041
 "MICHEL" SURVEY MARCH 3, 2013 *2013091083

DESCRIPTION

BEARING DISTANCE

1/2" x 16" REBAR W/CAP 16' TO E/P	NW	47.55'
1/2" x 16" REBAR W/CAP 1.5' TO FENCE	N	32.46'
FACE OF 8" x 14" BRIDGE BEAM FCP	N	25.8'
WOVEN WIRE FENCE	S	21'
37.60 BETWEEN REBARS		

"WALKER" SURVEY APRIL 18, 1995 # 95-07-0398


MONROE


68



2/12/18
DRM

SE CORNER
SECTION 1-31-7
MONROE TWP RT 39





SURVEY RECORD BOOK 2 (COPY) Pg 317 - STONE
OCT 16, 1867

ORIGINAL FIELD NOTE BOOK Pg 375 (1834)

DESCRIPTION


BEARING DISTANCE

4" x 7" I-BEAM FCP	NNW	56.7'
1/2" x 24" REBAR w/CAP 8' TO E/P	NE	46.65'
1/2" x 24" REBAR w/CAP 12' TO E/P	SE	50.46'

STONE-SURVEY RECORD BOOK 2 (COPY) Pg 175 - 1860

FRANKLIN

70



FO 3/4" IRON ROD 4" DEEP
SET MARK NAIL WITH CO
TAG OVER TOP

DESCRIPTION

BEARING DISTANCE

NAIL IN B. CAP IN POWER POLE	NW	21.75'
1/2" x 24" REBAR w/ CAP 16' TO E/P	NE	33.20'
1/2" x 24" REBAR w/ CAP 5.3' TO E/P	SE	37.75'

"WEAVER" SURVEY 1/16/1992 # 92-02-0048


OAK RIDGE S.D. AUGUST 1, 1972

SURVEY RECORD BOOK 3 P. 262 1928

" " " 3 P. 286 MAY 26, 1944

TURKEY CREEK

72



DESCRIPTION

BEARING

DISTANCE

NAIL IN B. CAP IN REMC POLE 1523

WSW

37.36'


NAIL IN B. CAP IN POWER POLE

SSW

69.85'

TURKEY CREEK

73



2/22/18

JRM

N 1/4 CORNER
SECTION 18-34-7
TURKEY CREEK TWP R 54

CR 1200 N

21' ASPH

YARD

CR 450 E


YARD

FO BR SPIKE 3" DEEP

"WALKER" SURVEY 9/25/2013 #2013091099

TURKEY CREEK

14




DESCRIPTION

BEARING DISTANCE

1/2" x 24" REBAR W/CAP 15' TO E/P 450E	NW	48.13'
NAIL IN B. CAP IN POWER POLE	SW	42.41'
1/2" x 24" REBAR W/CAP IN ROOT OF OAK TREE	WSW	57.18'

TURKEY CREEK

75



DESCRIPTION


BEARING DISTANCE

1/2" REBAR W/CAP	NW	42.00'
1/2" x 1/6" REBAR W/CAP 2' FROM B/C	NE	48.60'
1/2" x 1/6" REBAR W/CAP 2' FROM B/C	SW	31.23'
± FIRE HYDRANT	SW	33.2'

6/6/18 - SET HARRISON MONUMENT OVER 1" IRON PIN 8" DEEP

PLAIN

76



SEE FIELD BOOK 1 Pg 55 - 6/18/92


DESCRIPTION

BEARING DISTANCE

NAIL IN B. CAP IN POWER POLE	ENE	58.65'
NAIL IN B. CAP IN POWER POLE	NNE	78.16'
1/2" x 16" REBAR W/CAP 13' TO E/P 300 N	WSW	69.22'
1/2" x 16" REBAR W/CAP 21.3' TO E/P 200 W	SW	67.25'
FO NAIL IN TAG ON TOP OF 12" DIA WOOD FCP	NW	42.46'
FO NAIL IN B. CAP BESIDE MAG NAIL P. POLE	SSE	72.55'

SEE SECTION CORNER FIELD BOOK 2 P. 47 - 8/14/92

PLAIN



DESCRIPTION


BEARING DISTANCE

DESCRIPTION	BEARING	DISTANCE
RAILROAD RAIL FCP	W	19.25'
NAIL IN B CAP IN POWER POLE	W	18.09'
1/2" x 24" REBAR W/CAP S. 3' TO RR FCP	SE	33.18'

OLD TIE - RIP 19' W

TURKEY CREEK


78



2/28/18

JRM

S 1/4 CORNER
SECTION 18-34-7
TURKEY CREEK TWP PT 80



FOR RR SPIKE 4" DEEP

SET MAG NAIL W/TAG
OVER TOP